KADUR DIVISION.

Abstract Notification dated 14th March 1940.

The attention of the public is invited to the Notification published on pages 590-592, Part VI of the *Mysore Gazette*, dated 21st March 1940, calling for tenders for the works connected with the "Tarring of Kadur-Mangalore Road in front of Coffee Curing Works at Chikmagalur."

The last date of receipt of tenders in this office is 6th April 1940.

Notification dated 25th March 1940.

1. Sealed tenders will be received at the Office of the Executive Engineer, Kadur Division, Chikmagalur, up to 3 P.M. on 15th April 1940 for the work of improvements to entrance to Chikmagalur Town by widening the road and Bridge across wasteweir in 8/153 of Kadur-Mangalore Road at Chikmagalur.

2. Tenders in the prescribed form obtainable in the Office of the Executive Engineer, Kadur Division, Chikmagalur, on payment of annas four per each copy should be addressed to the Executive Engineer, Kadur Division, Chikmagalur, and should be superscribed as "Tender for the work of improvements to entrance to Chikmagalur Town by widening the road and bridge across waste weir in 8/153 of Kadur-Mangalore Road, Chikmagalur." The name of the tenderer should also be superscribed on the sealed cover.

3. Each tender should be accompanied by a treasury challan for Rs. 720 (rupees three hundred and twenty), only, credited to 17(*a*) P. W. deposits in any approved Government Treasury. The earnest money of the successful tenderer will be retained as cash security for the due fulfilment of the contract. Cash amount will not carry any interest.

4. The tenders will be opened in the presence of such tenderers who wish to be present on the date at the time of opening. The final acceptance of the tender will rest with the Executive Engineer, Kadur Division, who does not bind himself to accept the lowest or any tender, or to assign any reasons whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Office of the Executive Engineer in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute the agreement in the departmental schedule contract form, for the due fulfilment of the contract.

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. Copies of contract documents, estimates and drawings may be seen at any time at the Office of the Executive Engineer, Kadur Division, Chikmagalur, on all working days between 11 A.M. and 5 P.M.

8. Specific rates should be given for each item in the schedule and the rates should be in rupees, annas and pies and expressed in words and figures.

9. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer will not be taken notice of. The rates tendered should include all such lumpsum items.

10. No alterations which are made by the tenderers in the contract documents, in the nomenclature of the sanctioned sub-heads will be recognised and if corrections are made, the tenders will be liable to rejection.

11. There should be no corrections or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

12. No reference should be made to the Public Works Department current schedule of rates.

13. In the event of the tender being submitted by a firm, it must be signed separately and severally by each member therefor or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney authorising him to do so.

14. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates to be proposed by the Executive Engineer, Kadur Division, and approved by the Superintending Engineer shall be final and legally binding on the tenderer.

15. The quantities in estimates are only approximate and are liable to alterations, omissions, deductions or additions, at the discretion of the Executive Engineer, Kadur Division, or his representative. The tendered rates will hold good for any quantity whether it is higher or lower than those estimated for.

16. The work should be completed as per departmental specifications for different items and be handed over to the Public Works Department by the end of June 1940, failing which the Executive Engineer may, at his discretion, levy a penalty up to Rs. 100 which will be recovered from the contractor's outstandings for the period exceeded by him over the time specified above.

17. In all matters of dispute of any kind not specially provided for in the agreement or of rates, penalties, measurements, quantity of work, etc., the decision of the Executive Engineer Kadur Division, shall be final and legally binding.

18. The earnest money of rejected tenders will be returned on surrender of the receipts originally granted, along with an application to the Executive Engineer, Kadur Division, Chikmagalur.

19. No claims for damages for delays caused by officers of the department in the execution of work will be considered, whatever may be the reason for such delays. Contractors should bear this in mind when tendering for work. Extension of time due to delays caused by the departmental officers will be however, considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools, plant and machinery that will be supplied by the department in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer, and the tenderer will pay the hire, etc., on machinery at the prescribed per cent per annum of the booked value of the tools and plant supplied from the date of taking over of tools and plant from the Stores to the date of return to the Stores, the dates considered being the dates of acknowledgements of the vouchers in each transaction.

22. The Chamundi Brand cement must be used for the work.

23. The contractors should arrange for the payment of royalty and tolls.

Abstract estimate for Improvements to entrance to Chickmagalur Town by widening the road and bridge across waste weir in 8/153 of Kadur-Mangalore Road.

Item No.	Description of work	Unit	Rate	Quantity	Cost
	I. Widening the Bridge.		Rs. a. p.		Rs.
1	Dismantling the existing masonry parapet walls and removing debris	L.S.			
2	Earthwork excavation in hand gravelly soil mixed with boulder and using the same for road	C.yd.	0 5 6	76	
3	Laying stone jelly concrete in surki combination mortar	C.ft.	0 5 6	596	
4	Size stone in surki mortar with bond stones 6' apart	,,	0 7 0	3,062	
5	Providing and casting reinforced cement concrete bearing slabs 1 : 3 : 6 with necessary reinforcement of ½" diameter iron bars at 9" centre to centre on site and exposed faces plastered smooth with cement plaster	,,	1 4 0	51	
6	Providing, hoisting and fixing Tata's tested quality R.S. Girders (20"×6½") including anchoring and fixing with 2 coats of anti-corrosive paint	Cwt.	18 0 0	50.5	
7	R.C.C. decking 1 : 2 : 4 cast in site with necessary reinforcements of approved design including centering charges, etc., complete with exposed faces finished with nice cement plaster	C.ft.	2 0 0	358	
8	Providing expansion joints ½" thick fixed with approved material	R.ft.	0 8 0	37	
9	Pointing exposed faces of masonry with 1 : 3 cement mortar after raking joints 1" deep	Sqr.	4 0 0	4·55	
10	Providing hand railings with three rows of G.I. pipes 1¼" diameter and with angle iron uprights at 6' intervals as per design including ornamental pillars at ends as per approved design	R.ft.	2 12 0	98	
11	New rough stone work including jelly wedging	C.yd.	2 0 0	133	
	II. Widening the embankment.				
1	Earthwork for widening the bank at the approach of bridge including watering and consolidating with a lead of 2 furlongs	C.yd.	0 5 6	3,618	
2	Cutting grip trenches in the old bund after removing jungle	L.S.			
3	Turfing the newly formed rear slope of bund	S.yd.	0 0 9	1,394	
4	Providing new rough stone revetment at rear toe of bund including lead	C.yd.	2 0 0	208	
5	Removing and refixing railings	R.ft.	0 0 6	350	

Item No.	Description of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		
	III. *Metalling the Road.*				
1	Collecting and stacking boulders 2″ size for soling ..	C.yd.	1 0 0	65	
2	Consolidation of soling metal	,,	0 6 0	65	
3	Collecting, breaking, carting and stacking burnt metal 1½″ size with a lead of 3 furlongs ..	,,	3 4 0	74	
4	Spreading and consolidating of metal	,,	0 6 0	74	
5	Collecting spreading and consolidating gravel ..	,,	0 9 0	25	
6	Collecting and spreading sand	,,	0 10 6	6	
	Alternative items that may be found necessary consistent with changes that may be made during execution.				
1	Benching in hard rock for seating of foundations— 3″ to 6″ deep—				
	3″ deep	S.ft.	0 4 0	..	
	4½″ deep	,,	0 6 0	..	
	6″ deep	,,	0 8 0	..	
2	Exacavating in stoney soil and soft rock	C.yd.	0 6 0	..	
3	Size stone in surki cement combination mortar (1 : 8) proportion with bond stones 6′ apart in every course	C.ft.	0 8 0	..	
4	Constructing burnt brick in lime mortar parapet walls 1½′ thick and 2′ high of approved design with ornamental plasters at ends, including plastering, white-washing, etc., complete	R.ft.	1 4 0	..	
5	Constructing size stone in lime mortar pedestals of approved design 2′×2′×2½′ at ends, with coping slabs on top (1½′×1½′×6″)	No.	6 0 0	..	
6	Burnt stone slabs 6″ thick neatly dressed and fixed in pedestals vertically	S.ft.	0 10 0	..	

M. A. RAMANUJAM,
Executive Engineer.

CHITALDRUG DIVISION.

Notification dated 25th March 1940.

1. Sealed tenders will be received at the Office of the Executive Engineer, Chitaldrug Division, up to 3 P.M. on 10th April 1940, for constructing a bridge across left Waste Weir Valley of Dharampur Tank, Hiriyur Taluk.

2. Tenders in the prescribed form obtainable from the Office of the Executive Engineer, Chitaldrug Division, should be addressed to the Executive Engineer, Chitaldrug Division, in a sealed cover and superscribed as "Tender for constructing a bridge across left Waste Weir Valley of Dharampur Tank, Hiriyur Taluk." The name of the tenderer should also be superscribed on the top of the cover.

3. Each tender must be accompanied by a treasury challan for having credited to "17 (a) P.W. Deposits" a sum of Rs. 220 (Rupees two hundred and twenty only) in cash or Government Promissory Notes or Mysore Government Bonds, duly endorsed at face value or market value, whichever is less, as earnest money. The earnest money of the successful tenderer will be retained as security deposit for the due fulfilment of the contract. Such a deposit in cash will not carry any interest.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 10th April 1940 at 3 P.M. The final acceptance of the tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the departmental Schedule Contract Form for the due fulfilment of the contract, and for the execution of all items of work in accordance with the Bombay Specifications (1931).

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.